

Ditching & Adding Fabric and Gravel Scope of Work

Approximately 1000 feet of ditching to be done on Knights Pond Road
Approximately 3700 feet of fabric to be laid and 4300 yards of gravel

Ditching & Adding Fabric and Gravel Specifications

1. The bottom of the ditch 30" deep if possible, compacted and rounded
2. Uniform grade to prevent ponding of water
3. Two foot (2') shoulder
4. 2 to 1 in-slope
5. 2 to 1 back-slope
6. Adding fabric and gravel to a depth of 18" and width of 20', add in for slope to total approximately 3700 feet of gravel that meets state recommended specifications
7. Contractor is responsible for seeding ditches
8. The Contractor shall supply its own safety control, traffic control, and proof of \$1,000,000.00 Liability insurance.
9. Work can begin immediately after the bid is awarded and must be complete by October 11, 2024.
10. Contact the Road Commissioner, Amon Morse, with questions before bidding: 207-322-3331
11. The Town's Road Commissioner shall inspect and approve all work done before payment is made.