

Ditching & Culvert Replacement Scope of Work

Approximately 9287 feet of ditching and 11 culverts to be replaced, broken down as follows:

Ditching

| | |
|----------------|--------------------------------------|
| Verona St | 1030 feet |
| Bayside Rd | 307 feet (finishing on Cross Street) |
| Cross St | 520 feet |
| Broadway | 600 feet |
| Bayview St | 900 feet |
| Upper Bluff Rd | 2000 feet |
| Beech Hill Rd | 1665 feet |
| Shore Rd | 2265 feet |

Culverts

All culverts to be double-wall plastic and supplied by the Town

6 driveway culverts on Cross Street –

- 3 18"x30'
- 1 18"x80'
- 1 18"x40'
- 1 18"x50'

1 driveway culvert 15"x30' on Bayside Rd

3 driveway culverts 15"x30' on Broadway

1 driveway culvert 15"x30' on Beech Hill Rd

Ditching & Culvert Replacement Specifications

1. The bottom of the ditch 30" deep if possible, compacted and rounded
2. Uniform grade to prevent ponding of water
3. Two foot (2') shoulder
4. 2 to 1 in-slope; 2 to 1 back-slope
5. Cross culverts must be down to allow for at least 2 feet of material on top and rocked in around inlet and outlet.
6. Driveway culverts must be down to allow for at least 1 foot of material on top.
7. 2" minus used for back fill
8. 3' minimum of culvert for edge of travelled way to ditch
9. The Contractor shall supply its own safety control, traffic control, and proof of \$1,000,000.00 Liability insurance.
10. Work can begin immediately after the bid is awarded and must be complete by October 11, 2024.
11. Contact the Road Commissioner, Amon Morse, with questions before bidding: 207-322-3331
12. The Town's Road Commissioner shall inspect and approve all work done before payment is made.
13. The Contractor is responsible for becoming familiar with the location and extent of work to be performed. The Road Commissioner will be available to assist with this.