

Schoolhouse Brook Bridge Widening for Sidewalks

Scope of Work

Widen both upstream and downstream sides of existing bridge over Schoolhouse Brook on Bayside Road to add ADA and Maine DOT compliant sidewalks on both sides of the street.

Specifications:

1. Contractor must supply their own safety control, traffic and pedestrian control measures, and proof of worker's compensation and liability insurance in the amount of \$1,000,000.
2. Contractor must conform with MUTCD.
3. Outside edge of each sidewalk to be separated from stream by wooden guardrail (pressure-treated 8"x8" post and 3"x10" rail), 30" high to top of rail.
4. Sidewalk to consist of 2" of pavement (hot mix asphalt) over subbase gravel. Sidewalk to be 4' wide, with running slope no more than 8.33%. Level of sidewalk to be flush with top of bituminous curb, 6" above existing road surface.
5. Existing guardrails on both sides to be removed. Existing shrubs on downstream side to be removed for replanting by abutter.
6. Contact the Road Commissioner, Amon Morse, with questions before bidding: 207-322-3331
7. All work will be inspected and approved by the Road Commissioner before payment is made.
8. The Contractor is responsible for becoming familiar with the locations and extent of work to be performed.
9. Work can begin immediately upon awarding and must be complete by October 11, 2025.