

Town of Northport

2026 Brush Cutting — Scope of Work

Areas of Work

The contractor shall perform brush cutting on both sides of the roadway or designated areas at the following locations:

1. **Knights Pond Road**
Starting at Beech Hill Road and continuing to Mailbox #100. Work shall be performed on both sides of the road. Brush is expected to be spotty, with certain sections being denser than others.
2. **Beech Hill Road**
Starting at Route 52 and continuing to Knights Pond Road. Work shall be performed on both sides of the road. Brush is expected to be spotty, with certain sections being denser than others.
3. **Nebraska Road**
From the beginning of the designated work area all the way to the gate. Work shall be performed on both sides of the road.
4. **Beach Ridge Cemetery — off Nebraska Road**
Brush cutting shall be performed on both sides of the road/drive within the cemetery area through to the end of the cemetery.
5. **Shore Road — 689 Shore Road**
One specific area just before Kelly Cove shall be cut.
6. **Shore Road — Kelly Cove to 640 Shore Road**
Starting at Kelly Cove and continuing south to 640 Shore Road. Work shall be performed on both sides of the road.
7. **Shore Road — 473 Shore Road to 154 Shore Road**
Brush cutting shall begin at 473 Shore Road and continue to 154 Shore Road. Brush is expected to be spotty. Work shall be performed on both sides of the road.
8. **Pound Hill**
Starting at Route 1 and continuing to the Upper Bluff intersection. Work shall be performed on both sides of the road.
9. **Saturday Cover Road**
Starting at Route 1 and continuing to Mailbox #26. Work shall be performed on both sides of the road, with the majority of the work expected to be on the left side of the road.

Work Specifications

The contractor shall perform all work in accordance with the following specifications:

- Brush shall be cut back to the **top/back of the ditch line or a maximum of 20 feet**, as conditions allow.
- Brush and woody vegetation **6 inches in diameter or smaller** shall be cut.

- Brush shall be cut **as close to the ground as reasonably possible**, leaving no sharp points or hazardous stubs.
- Limbs and branches overhanging the roadway or ditch shall be trimmed back to the existing tree line to provide a minimum clearance of **14 feet in height**.
- All cut brush, limbs, and vegetation shall be **chipped or removed from the site** by the contractor.
- The contractor shall leave all work areas in a clean and orderly condition upon completion.
- Care shall be taken to avoid damage to road surfaces, drainage ditches, trees intended to remain, utility infrastructure, mailboxes, signs, and other public or private property.

4. Contractor Responsibility

The contractor shall provide all necessary labor, equipment, tools, transportation, chipping equipment, and disposal necessary to complete the work described in this Scope of Work.

The contractor is responsible for properly managing and removing all resulting brush and debris generated by the work.

All work shall be performed in a manner that maintains safe conditions for the traveling public, pedestrians, Town personnel, and the contractor's employees.

5. Completion

All specified work shall be completed to the satisfaction of the Town of Northport. The Town reserves the right to inspect completed work and require correction of areas that do not meet the specifications outlined above.